Bill of Qunatities

Name of Project: Upgrading of Nepali nahar dekhi Hosna tole hundai Saraswati ma. Vi. Jodne sadak , Bardaghat -15 , Nawalparasi .
Location :-Bardaghat Muncipality , Nawalparasi.
Contract ID :-RIDONAW/134/NCB/083-84/11

S. No.	Description	Unit	Quantity	Quoted Rate		Amount
				In Figure	In Words	
1.0	**Provisional Sum**					
1.1	Off site verification testing (not specified in specifications) of materials/works as directed by the Engineer.	PS	1.00	5000.00	Five Thousands Only.	5,000.00
1.2	Insurance of works, equipment, Contractor's workmen and employees and Third party Insurance against damage to other persons and property.(SSG18)	PS	1.00	20000.00	Twenty Thousands Only.	20,000.00
2.0	**General**					
2.1	Supply and place and maintain standard size (1.20 x 0.90 m) sign board for Project information.	Nos	1.00			
3	**Pavement work**					
3.1	Providing, laying, spreading, watering and compacting embankment with Roadway Cutting material and compact to the required density as per drawing and Technical Specifications. (Mechanical Means)	m3	318.00			
3.2	Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density by mechanical means, complete as per Drawing and Technical Specifications.	m3	652.50			
4	**Structure Work**					
4.1	Earthwork in excavation of foundation of structure in ordinary soil including construction of shoring and bracing, removal of stumps and other deleterius matter and backfilling with approved material as per drawings and technical specifications.	m3	62.13			
4.2	Providing and laying of hand pack Stone soling with 150 to 200 mm thick stones and packing with smaller stone on prepared surface as per Drawing and Technical Specifications.	m3	8.79			
4.3	Providing and laying of Plain Cement Concrete M 10 (or 1:3:6 for Nominal Mix) in foundation complete as per Drawing and Technical Specifications	m3	12.20			
4.4	Providing and laying Plum Concrete mixing of 60% M15 concrete and 40% boulder/stones (Boulder mixed concrete) including formwork and pipes for weep holes etc all complete as per Drawing and Technical Specifications.	m3	70.50			
4.5	Providing and Laying RCC 450 mm dia NP3 Flush jointed pipe for culvert including fixing with cement mortar 1:2 as per drawing and technical specifications	Rm	15.00			
4.6	Providing and Laying RCC 900 mm dia NP3 Flush jointed pipe for culvert including fixing with cement mortar 1:2 as per drawing and technical specifications	Rm	7.50			
	(A) Total Cost without PS					
	(B) 13 % @ VAT=13% of A					
	(C) PS Amount					
	(D) Total Cost with PS and VAT=A+B+C					