Bill of Qunatities

Name of Project: Upgrading of i) Subidar chauk dekhi Paschim Thaman ko ghar bata uttar Park samma jane Sadak, Bardaghat -4, ii) Aadarsanagar Chauk dekhi dakshin jane sadak , Bardaghat-4, Nawalparasi .
Location :-Bardaghat Muncipality ,Nawalparasi.
Contract ID :-RIDONAW/134/NCB/083-84/04

S. No.	Description	Unit	Quantity	Quoted Rate		Amount
				In Figure	In Words	
1.0	**Provisional Sum**					
1.1	Off site verification testing (not specified in specifications) of materials/works as directed by the Engineer.	PS	1.00	10000.00	Ten Thousands Only.	10,000.00
1.2	Insurance of works, equipment, Contractor's workmen and employees and Third party Insurance against damage to other persons and property.(SSG18)	PS	1.00	17500.00	Seventeen Thousand Five Hundred Only.	17,500.00
2.0	**General**					
2.1	Supply and place and maintain standard size (1.20 x 0.90 m) sign board for Project information.	Nos	2.00			
3.0	**Pavement work**					
3.1	Loosening, levelling, and compacting original ground supporting embankment to facilitate placement of first layer of embankment, scarified to a depth of 150 mm, mixed with water at OMC and then compacted by rolling so as to achieve dry density as per Drawing and Technical Specification	m2	1135.50			
3.2	Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density by mechanical means, complete as per Drawing and Technical Specifications.	m2	113.55			
3.3	Providing and laying of Ready Mix Plain/Reinforced Cement Concrete in foundation all complete as per Drawing and Technical Specifications (SS 2000), M25 Grade	m3	170.32			
3.4	Providing, preparing and installing Formwork including necessary supports and removing after completion as per specification.(1804,1805)	m2	62.55			
3.5	Providing and laying, fitting and placing HYSD bar reinforcement in foundation all complete as per Drawing and Technical Specifications (SS Clause 2014)	Kg	2124.84			
	(A) Total Cost without PS					
	(B) 13 % @ VAT=13% of A					
	(C) PS Amount					
	(D) Total Cost with PS and VAT=A+B+C					