Bill of Qunatities

Name of Project: Upgrading of i) Bihari Sadak Sunwal-4 , ii) Sarbottam cement karkhana ko Gate dekhi Siyari Jane sadak, Sunwal -4 , Nawalparasi. , Nawalparasi .

Location :-Sunwal Muncipality , Nawalparasi.

Contract ID :-RIDONAW/134/NCB/083-84/08

S. No.	Description	Unit	Quantity	Quoted Rate		Amount
				In Figure	In Words	
1.0	**Provisional Sum**					
1.1	Off site verification testing (not specified in specifications) of materials/works as directed by the Engineer.	PS	1.00	10000.00	Ten Thousands Only.	10,000.00
1.2	Insurance of works, equipment, Contractor's workmen and employees and Third party Insurance against damage to other persons and property.(SSG18)	PS	1.00	20000.00	Twenty Thousands Only.	20,000.00
2.0	**General**					
2.1	Supply and place and maintain standard size (1.20 x 0.90 m) sign board for Project information.	Nos	2.00			
3	**Pavement work**					
3.1	Providing, laying, spreading, watering and compacting embankment with Roadway Cutting material and compact to the required density as per drawing and Technical Specifications. (Mechanical Means)	m^3	1348.80			
3.2	Providing and laying granular sub-base on prepared surface, mixing at OMC, and compacting to achieve the desired density by mechanical means, complete as per Drawing and Technical Specifications.	m^3	1011.60			
	(A) Total Cost without PS					
	(B) 13 % @ VAT=13% of A					
	(C) PS Amount					
	(D) Total Cost with PS and VAT=A+B+C					